

Project Profile:

Blackfriars Bridge Foreshore

MAIN CONTRACTOR	Thames Tideway Tunnel
CLIENT	VolkerStevin
CONTRACT VALUE	£1,000,000

McNealy Brown Ltd were contracted to design, fabricate, finish, deliver & install the following works: -

- **St Pauls Walk, Blackfriars Embankment: Tunnel Strengthening, Access Ramp & Stairs, Emergency Gate**
- **Blackfriars Road Bridge Lift Stair**
- **Tattershall Castle Access Stairs**

All of the fabrication was carried out at our workshop in Sittingbourne and was followed by trial erection of the Blackfriars Access Ramp & Stairs, Lift Stair & Tattershall Castle Access Stairs.

Additional works carried out included:

- Stainless Steel Satin Finish Luminaire Handrails supplied & installed by DW Windsor (Ramp & Stairs) & Handrail Design Ltd (Lift Stair).
- Stainless Steel Satin Finish Handrails (Tattershall Castle) by McNealy Brown Ltd.
- Transition Plate Assemblies (Tattershall Castle).
- Resin Filled Anti – Slip Stainless Steel Ramp Planks & Landing Plates (Ramp & Stairs, Tattershall Access Stairs).
- Secondary Granite Cladding Support Steelwork (Ramp & Stairs, Tattershall Access Stairs).
- Plant Room under the Lift Stair.
- Copper Nickel Cladding Panels (Lift Stair).

All the main steel works were delivered to Silvertown holding yard by lorry & then delivered to site by barge and installed using either a jack up crane or barge crane in the Thames.

This Project took 18 months from order to completion.



McNealyBrown
LIMITED

SPECIALIST FABRICATORS ARCHITECTURAL METALWORKERS DESIGN & INSTALLATION ENGINEERS

Units 14-17 Craft Marsh Trading Estate, Gas Road, Sittingbourne, Kent, ME10 2QB
Tel. 01795 470592 info@mcnealybrown.co.uk www.mcnealybrown.co.uk